Dam:	Cana Brava	Country	Brazil
River	Tocantins	13°24'8.06"S 48°8'36.64"W	-13.402239 -48.143513
Owner/Client	Companhia Energética Mercosul (of the Tractebel Group)		
Designer/Engineer	Intertechne Consultores Associasdos		
Contractor	Construtora Norberto Odebrecht S.A., Andrade Gutierrez J.V.		

Purpose (code)	H
Site start	01.03.1999
RCC start	01.02.2000
RCC completion	31.10.2001
Site completion	31.10.2002
Height (m)	67
Length (m)	510
Volume of RCC (m^3x10^3)	527
Total volume (m^3x10^3)	833
Reservoir capacity (m^3x10^6)	2300
Upstream slope	*Unknown*
Forming of upstream face (code)	(1)
Downstream slope	*Unknown*
Forming of downstream face (code)	(3) *
Spillway slope	ogee
Forming of spillway face (code)	(1)
Depth of layers (mm)	300
Depth of lifts (mm)	300
Cement content (kg/m^3)	40
Pozzolan content (kg/m^3)	50
Code for pozzolan	(S)
RCCDAM Unique Serial No.	RCCDAM0255

Under Construction



RCCDAM0255UC

Completed Dam



RCCDAM0255CD

Google Earth



RCCDAM0255GE

Guide to Abbreviations

Purpose

E	Environmental
F	Flood control
G	Groundwater recharge
H	Flood control
I	Irrigation
N	Navigation
P	Pollution control
R	Recreation
W	Water supply

Facing method

(1)	Traditional concrete against formwork
(2)	Traditional concrete against formwork with external geomembrane
(3)	RCC against formwork
(4)	RCC against formwork with external geomembrane
(5)	Traditional concrete against precast concrete panels
(6)	Traditional concrete against precast concrete panels with geomembrane
(7)	RCC against precast concrete panels
(8)	RCC against precast concrete panels with geomembrane
(9)	RCC against precast concrete panels with hot poured membrane
(10)	RCC against precast concrete blocks
(11)	Reinforced conventional concrete cast before RCC placement
(12)	Reinforced conventional concrete cast after RCC placement
(13)	Reinforced concrete cast against precast units or slip-formed facing elements
(14)	Slip-formed/extruded facing elements
(15)	RCC supported by fill shoulders
(16)	Mechanically compacted unformed face of RCC
(17)	Unformed face of RCC
'	GEVR/GE-RCC
*	Stepped face

Pozzolans

(-)	No Pozzolan Used
(C)	High-lime flyash (ASTM Class C)
(F)	Low-lime flyash (ASTM Class F)
(M)	Milled sand
(N)	Natural pozzolan (ASTM Class N)
(R)	ROLAC (mixture of flyash and slag with or without limestone fines)
(S)	Ground-granulated blast-furnace slag
(L)	Mixture of GGBFS and limestone fines