Dam:	Enciso	Country	Spain
River	Cidacos	42°08'40.66"N 2°16'39.21"W	42.144627 -2.277558
Owner/Client	Confederación Hidrográfica del Ebro, Ministerio de Agricultura Alimentación y Medio Ambiente		
Designer/Engineer	Confederación Hidrográfica del Ebro and Typsa/Sering JV		
Contractor	Dragados S.A./FCC J.V		

Purpose (code)	I W
Site start	01.07.2008
RCC start	19.08.2014
RCC completion	19.07.2017
Site completion	30.09.2018
Height (m)	103
Length (m)	376
Volume of RCC (m^3x10^3)	698
Total volume (m^3x10^3)	765
Reservoir capacity (m^3x10^6)	47
Upstream slope	V
Forming of upstream face (code)	(1)
Downstream slope	0.80
Forming of downstream face (code)	(1) *
Spillway slope	0.80
Forming of spillway face (code)	(1) *
Depth of layers (mm)	300
Depth of lifts (mm)	300
Cement content (kg/m^3)	60
Pozzolan content (kg/m^3)	140
Code for pozzolan	(F)
RCCDAM Unique Serial No.	RCCDAM0642

Under Construction



RCCDAM0642UC

Completed Dam



RCCDAM0642CD

Google Earth



RCCDAM0642GE

Guide to Abbreviations

Purpose

E	Environmental
F	Flood control
G	Groundwater recharge
H	Flood control
I	Irrigation
N	Navigation
P	Pollution control
R	Recreation
W	Water supply

Facing method

(1)	Traditional concrete against formwork
(2)	Traditional concrete against formwork with external geomembrane
(3)	RCC against formwork
(4)	RCC against formwork with external geomembrane
(5)	Traditional concrete against precast concrete panels
(6)	Traditional concrete against precast concrete panels with geomembrane
(7)	RCC against precast concrete panels
(8)	RCC against precast concrete panels with geomembrane
(9)	RCC against precast concrete panels with hot poured membrane
(10)	RCC against precast concrete blocks
(11)	Reinforced conventional concrete cast before RCC placement
(12)	Reinforced conventional concrete cast after RCC placement
(13)	Reinforced concrete cast against precast units or slip-formed facing elements
(14)	Slip-formed/extruded facing elements
(15)	RCC supported by fill shoulders
(16)	Mechanically compacted unformed face of RCC
(17)	Unformed face of RCC
'	GEVR/GE-RCC
*	Stepped face

Pozzolans

(-)	No Pozzolan Used
(C)	High-lime flyash (ASTM Class C)
(F)	Low-lime flyash (ASTM Class F)
(M)	Milled sand
(N)	Natural pozzolan (ASTM Class N)
(R)	ROLAC (mixture of flyash and slag with or without limestone fines)
(S)	Ground-granulated blast-furnace slag
(L)	Mixture of GGBFS and limestone fines