

Dam: Huatan

Country: China

River: Yinghe

DMS Co-ordinates: Unknown

DD Co-ordinates: Unknown

Owner/Client: Ya'an Electricity Company

Designer/Engineer: Investigation and Design Institute of Hydropower, Sichuan Province

Contractor: 10th Construction Bureau, MOE & MWR

Purpose (code): H

Site start: 01.01.1996

RCC start: 01.06.1996

RCC completion: 30.12.1998

Site completion: 01.05.1999

Height (m): 85

Length (m): 173

Volume of RCC (m<sup>3</sup>x10<sup>3</sup>): 240

Total volume (m<sup>3</sup>x10<sup>3</sup>): 290

Reservoir capacity (m<sup>3</sup>x10<sup>6</sup>): 8

Upstream slope: 0.20

Forming of upstream face (code): (1)

Downstream slope: 0.80

Forming of downstream face (code): (1)

Spillway slope: 0.80

Forming of spillway face (code): (1)

Depth of layers (mm): 300 - 400

Depth of lifts (mm): 300 - 400

Cement content (kg/m<sup>3</sup>): 78 - 74

Pozzolan content (kg/m<sup>3</sup>): 95 - 90

Code for pozzolan: (F)

RCCDAM Unique Serial No.: RCCDAM0205

### Completed Dam



RCCDAM0205CD

# Guide to Abbreviations

## Purpose

- E Environmental
- F Flood control
- G Groundwater recharge
- H Flood control
- I Irrigation
- N Navigation
- P Pollution control
- R Recreation
- W Water supply

## Facing method

- (1) Traditional concrete against formwork
- (2) Traditional concrete against formwork with external geomembrane
- (3) RCC against formwork
- (4) RCC against formwork with external geomembrane
- (5) Traditional concrete against precast concrete panels
- (6) Traditional concrete against precast concrete panels with geomembrane
- (7) RCC against precast concrete panels
- (8) RCC against precast concrete panels with geomembrane
- (9) RCC against precast concrete panels with hot poured membrane
- (10) RCC against precast concrete blocks
- (11) Reinforced conventional concrete cast before RCC placement
- (12) Reinforced conventional concrete cast after RCC placement
- (13) Reinforced concrete cast against precast units or slip-formed facing elements
- (14) Slip-formed/extruded facing elements
- (15) RCC supported by fill shoulders
- (16) Mechanically compacted unformed face of RCC
- (17) Unformed face of RCC
  - ' GEVR/GE-RCC
  - \* Stepped face

## Pozzolans

- (-) No Pozzolan Used
- (C) High-lime flyash (ASTM Class C)
- (F) Low-lime flyash (ASTM Class F)
- (M) Milled sand
- (N) Natural pozzolan (ASTM Class N)
- (R) ROLAC (mixture of flyash and slag with or without limestone fines)
- (S) Ground-granulated blast-furnace slag
- (L) Mixture of GGBFS and limestone fines